Turkish Online Journal of Qualitative Inquiry (TOJQI) Volume 12, Issue 6, June 2021:335-348

Research Article

### Earned Value Management of a Villa Construction project using Primavera P6

V Thirumalai<sup>1</sup>, M Kothanda Ramjee<sup>2</sup>, SenthilPandian M<sup>3</sup>, Karthikeyan K<sup>4</sup>

#### Abstract

The Indian construction industry has still not recovered from the effects of demonetization and it has resulted in abrupt stoppage of construction work by many small and medium construction enterprises. Now the ensuing Covid-19 pandemic has brought the industry to a standstill and its impacts are yet to be analyzed. Effective project management is thus the need of the hour and the planning has to ensure the optimum use of budget and resources without compromising the quality of construction. Small construction enterprises in India solely depend on project managers to execute the design and do not invest in proper planning software. This sometimes can result in improper decision making, irregular scheduling, poor handling of the project which ultimately results in increased expenditure and wastage of available resources. To reduce such discrepancies, an effective tool called Primavera P6 is introduced to help optimize the planning and scheduling process for construction activities. This will help small construction enterprises accurately estimate the duration of completion, resource allocation and the budget associated with any activity and reduce cost outruns, thereby increasing the overall efficiency of the project completion process. This study aims to review the existing methods of construction management in small and medium construction firms by using Primavera P6 and perform Earned Value Management on a villa construction project.

*Keywords: Planning, Scheduling, Primavera P6, Resource allocation, Earned Value Management* 

<sup>&</sup>lt;sup>1</sup>vanirudh112@gmail.com

<sup>&</sup>lt;sup>2</sup>ramjeerodriguez1999@gmail.com

<sup>&</sup>lt;sup>3</sup> senthilpandian.m@vit.ac.in

<sup>&</sup>lt;sup>4</sup>karthikeyan.kothanda@vit.ac.in

## Introduction

**Construction project management** is the process or science of controlling the planning, design and execution of construction projects from start till completion. The significance of proper and precise construction project management is immense and unbounded. To avoid cost overruns, delays and conflict between the client and the contractor, construction project management is to be accurately performed. This is very important in small and medium scale construction firms where they cannot afford cost overruns, especially at a situation - like now - where the entire industry is down.

The impact of the Covid-19 pandemic on the infrastructure and construction sector in India has been extensive and damaging. The restrictions imposed by the government of India and various other state governments to control the spread and impact of the virus have extensively stunted work on projects and adversely impacted supply chains, plants, equipment, materials and manpower.

Potential recovery of the capital and work lost is contractually obligated and work needs to get back underway as soon as possible. Stressful situations like these only serve to further the workload on construction planners who are already overworked in trying to utilize the resources available for the project effectively. Relying on intuition, like a lot of smaller construction firms in India do, during unprecedented times like this can be catastrophic and hence should be avoided.

The main objectives of this study are:

- To highlight the importance of proper planning and monitoring of the work to be done
- To highlight the versatility and deftness of Primavera P6 as a project management tool
- Perform Earned Value Analysis for a villa construction project to backup conclusions

# Methodology

This study mainly focuses on performing Earned Value Management (EVM) on a villa construction project and in effect highlighting the compactness and fluidity of Primavera P6.

Earned value management is a project management technique used to monitor and measure project performance against planned and actual parameters. Integrated systems involving scope, cost and progress of the project help the management team assess and measure the performance of the project under consideration.

Earned value management involves a cost performance baseline against which the progress and scope of the project are measured and defined. The said baseline thus acts as a sort of measuring stick which helps in lending perspective to the management team. The resulting analysis is done via several work performance enhancements involving several project influencing parameters like projected cost, actual cost, project time, etc.

## Project Management hierarchy in Primavera P6





Fig 1. Hierarchy of project management

**Project portfolio:** is a collection of projects designed to facilitate viewing of multiple projects, one at a time. This helps in effective project management by grouping projects together to optimize the organizational output. Usually, a portfolio can be used to review the data and status information regarding organizational activities.

*Enterprise Project Structure (EPS):* represents the hierarchical structure of all projects in the organization. The EPS is the highest level of project management hierarchy and it can be subdivided into as many levels as needed to represent the entire work done by the organization.

*Work breakdown structure (WBS):* is an arrangement of the work to be done that divides the projects into discrete phases. This helps organize the project's total work into manageable sections.

*Steps:* are subsidiaries of project activities and are used to identify and report progress of an activity at different levels



# Project methodology/Work plan

Fig 2. Work plan

### Advantages of Earned Value Management system

- Helps clearly define scope of work to be done
- Establishes hierarchy of responsibility ensuring minimal missteps
- Provides novel method of integrating schedule, cost and scope
- Acts as a warning system in identifying potential problems
- Analyzes impact of known problems and helps manifest them in terms of cost and scope
- Establishes clear lines of communication across the managerial hierarchy
- Adds several welcome layers to project visibility

## Case Study: Villa at ECR

This case study serves a purpose in substantiating our observations and further helped us understand the workings of project managers in medium industries. The structure under consideration is a villa located on the East Coast Road.

The villa was constructed from around April of 2019 to February of 2020 and just missed the pandemic by a month. The structure is a RCC framed structure with the roof around 11 feet tall and 5 inches thick and the lintel beam around 8 feet high. The type of foundation used was an isolated footing and 11 such trapezoidal column footings were used.

The land area of the plan is around 1580 sq-ft and the subsequent built-up area is around 3000 sq-ft.

Project	Construction of a villa
Location of site	East Coast Road, Chennai
Type of building	Residential 4BHK
Additional features	Modular Kitchen
Land area	1580 sq-ft
Built-up area	3000 sq-ft
Main wall	9.5" thick
Partition wall	4.5" thick

Table 1. Villa at ECR - Case study details




Fig 3. Floor plan of the Villa

### Work done and results

- A *schedule* is first created to facilitate monitoring and reviewing of project activities
- To emulate structure of the contactor company, a temporary *EPS* was created in Primavera
- A corresponding *OBS* was then created to represent the hierarchy of responsibility for the project
- A *calendar* was then created which is assigned to the activities and resources to provide a timeline of the work to be done. Primavera P6 offers three types of calendars: *global calendar, project calendar* and *resource calendar*. For this particular study we used the *6x9 global calendar,* which represents a 6-day week with 9 hours of work per day

### Earned Value Management of a Villa Construction project using Primavera P6

Tota	l work ho	ours/day				C Det	ailed work hours/day		
<			May 202	1		>	Work hours/day	<ul> <li>Image: A start of the start of</li></ul>	ОК
Sun	Mon	Tue	Wed	Thr	Fri	Sat	9.0	0	Cancel
						1		(?)	Help
2	3	4	5	6	7	8			
9	10	11	12	13	14	15		2	Work
16	17	18	19	20	21	22		×	Nonwork
23	24	25	26	27	28	29		-	<u>S</u> tandard
30	31								Wo <u>r</u> kweek
Standar	d 🗌	Nonw	vork	Exc	eption				Time Periods
Inherit I	holidays	and exce	ptions fro	m Global	Calendar	-			
<none< td=""><td></td><td></td><td>20010 110</td><td></td><td>ousidu</td><td></td><td></td><td></td><td></td></none<>			20010 110		ousidu				

## Fig 4. 6X9 Global calendar

• Then project itself was created with a *WBS* attached to it. Similarly, several WBS elements were created each providing its own depth in the form of activities and steps

WBS		
Activities Project	s WBS	
✓ Layout: WBS		
WBS Code	L	WBS Name
⊟ 🗁 RB		Residential Building
RB.P		Preparation of Site
- 🖬 RB.S		Sub Structure
- 🖬 RB.I		Preparation of foundation
- 💾 RB.PL		Plinth Works
📲 RB.G		Ground Floor
📲 RB.F		First Floor
RB.T		Terrace
🗄 🖷 RB.E		Exterior Works
- 🖬 RB.E.PL		Plastering
- 🖷 RB.E.WAT		Water & Sanitation Works
RB.E.EW		Electrical works
- 🖬 RB.E.D		Doors & Windows fini
- 🖬 RB.E.FF		Floor finishes
- 🖷 RB.E.PA		Painting
RB.E.HO		Handing over
_		
<		>

Fig 5. Project Work Breakdown Structure

• The aforementioned *activities* were then defined to represent the fundamental working elements of the WBS. Each activity comprised of an *activity name, activity ID, start* and *finish dates* and the corresponding *duration*, constraints in the form of *successor/predecessor relationships, resource values*, etc.

∠ Layout: Classic Schedule Layout				Filter: All Activities					
Activity ID	Activity Name	Original Duration	Remaining Duration	Schedule %	Start <sub>V</sub>	Finish	1		
💼 RB Resid	lential Building	233	193	100%	04-Apr-19	01-Jan-20			
🗆 🖷 RB.P Pr	eparation of Site	8	0	100%	04-Apr-19.	12-Apr-19.			
😑 A1000	Surveying	2	0	100%	04-Apr-19.	05-Apr-19.	1		
😑 A1010	Marking Boundaries	1	0	100%	06-Apr-19.	06-Apr-19.			
😑 A1170	Temporary Connection	2	0	100%	08-Apr-19.	09-Apr-19.			
😑 A1030	Temprorary Main gate and fencing	1	0	100%	10-Apr-19.	10-Apr-19.			
😑 A1020	Borewell	2	0	100%	11-Apr-19.	12-Apr-19.			
🗉 🖷 RB.S Su	ib Structure	6	0	100%	13-Apr-19.	19-Apr-19.			
😑 A1040	Column layout marking	2	0	100%	13-Apr-19.	15-Apr-19.	1		
😑 A1050	Excavation	3	0	100%	16-Apr-19.	18-Apr-19.			
😑 A1060	Preparation of PCC works	1	0	100%	19-Apr-19.	19-Apr-19.			
😑 A1070	Soiling	1	0	100%	19-Apr-19.	19-Apr-19.			
😑 A1090	Pouring of PCC	1	0	100%	19-Apr-19.	19-Apr-19.			
🗉 🖬 RB.I Pre	eparation of foundation	9	0	100%	23-Apr-19.	02-May-19	I		
🗖 A1110	Layout Marking	1	0	100%	23-Apr-19.	23-Apr-19.	1		
😑 A1120	Laying of reinforcement	1	0	100%	24-Apr-19.	24-Apr-19.			
😑 A1130	Shuttering for Matt foundation and pou	1	0	100%	25-Apr-19.	25-Apr-19.			
😑 A1140	Shuttering for column	1	0	100%	26-Apr-19.	26-Apr-19.			
😑 A1150	Pouring of concrete	1	0	100%	27-Apr-19.	27-Apr-19.			
😑 A1810	Deshuttering	1	0	100%	29-Apr-19.	30-Apr-19.			
😑 A1860	Foundation column	2	0	100%	30-Apr-19.	01-May-19			
😑 A1870	Soil refilling	1	0	100%	02-May-19	02-May-19	۰,		

#### Activities


Activit		Classic	Schedule Layout Activity Name	Original Duration	Filter: All Ac Remaining Duration	Schedule %	Start <sub>77</sub>	Finish	Γ
-	R	B.PL	Plinth Works	26	0	100%	03-May-19	01-Jun-19	L
	_	A1160	Setting up level for plinth	1	0	100%	03-May-19	03-May-19	٦
		A1180	Laying of PCC	1	0	100%	04-May-19	04-May-19	
		A1190	Laying of reinforcement	2	0	100%	06-May-19	07-May-19	
		A1200	Side shuttering for beams	2	0	100%	08-May-19	09-May-19	
		A1210	Pouring of concrete	1	0	100%	10-May-19	10-May-19	
		A1220	Deshuttering	1	0	100%	17-May-19	17-May-19	
		A1230	Rising brickwork till floor level	2	0	100%	18-May-19	20-May-19	
		A1240	Backfilling upto plinth beam bottom	1	0	100%	21-May-19	22-May-19	
		A1250	Compaction of soil	3	0	100%	22-May-19	24-May-19	
		A1260	Laying of PCC	1	0	100%	25-May-19	25-May-19	
		A1880	Septic tank and sump works	6	0	100%	27-May-19	01-Jun-19	
	🖥 R	B.G C	Fround Floor	37	0	100%	03-Jun-19	15-Jul-197	
	-	A1300	Column raising upto roof level	4	0	100%	03-Jun-19	06-Jun-19	
		A1270	Staircase shuttering	1	0	100%	07-Jun-19	07-Jun-19	
		A1310	Roof shuttering	3	0	100%	08-Jun-19	11-Jun-19	
		A1280	Staircase barbending	1	0	100%	12-Jun-19	12-Jun-19	
		A1320	Roof Barbending	2	0	100%	13-Jun-19	14-Jun-19	
		A1290	Staircase waist slab concrete	1	0	100%	14-Jun-19	14-Jun-19	
		A1890	Roof levelling	1	0	100%	15-Jun-19	15-Jun-19	
		A1900	Eletrrical pipe laying	1	0	100%	15-Jun-19	15-Jun-19	
		A1330	Roof Concrete	1	0	100%	17-Jun-19	17-Jun-19	
		A1340	Deshuttering	1	0	100%	01-Jul-19.4	01-Jul-19,4	
		A1360	Brickwork upto lintel level	3	0	100%	02-Jul-19.4	04-Jul-19,4	ľ
		A1370	Rubble leveling	1	0	100%	05-Jul-197	05-Jul-197	ľ
		A1380	Lintel & Sunshade shuttering work	1	0	100%	06-Jul-197	06-Jul-197	[
		A1390	Lintel & Sunshade barbending work	1	0	100%	08-Jul-197	08-Jul-197	
		A1480	Lintel & Sunshade concrete	1	0	100%	09-Jul-197	09-Jul-197	
		A1850	Lintel & Sunshade deshuttering	1	0	100%	10-Jul-197	10-Jul-197	ľ
		A1820	Brick work till roof level	2	0	100%	11-Jul-197	12-Jul-197	
		A1910	Fixing of door and window frames	2	0	100%	13-Jul-197	15-Jul-197	


	assic S	chedule Lavout		Filter: All Ac	tivities		
ty ID		Activity Name	Original Duration		Schedule %	Start <sub>7</sub>	Finish
🖕 RB.	F Fi	rst Floor	37	0	100%	16-Jul-197	27-Aug-1
A1	400	Column raising upto roof level	4	0	100%	16-Jul-197	20-Jul-19
😑 A1	410	Staircase shuttering	1	0	100%	22-Jul-19/	22-Jul-19
😑 A1	440	Roof shuttering	3	0	100%	23-Jul-197	25-Jul-19
😑 A1	420	Staircase barbending	1	0	100%	26-Jul-197	27-Jul-19
😑 A1	450	Roof barbending	2	0	100%	27-Jul-197	29-Jul-19
😑 A1	430	Staircase waist slab concrete	1	0	100%	30-Jul-197	30-Jul-19
😑 A1	920	Roof Levelling	1	0	100%	30-Jul-197	30-Jul-19
😑 A1	930	Electrical Pipe Laying	1	0	100%	31-Jul-197	31-Jul-19
🗖 A1	460	Roof concrete	1	0	100%	01-Aug-19	01-Aug-1
😑 A1	470	Deshuttering	1	0		14-Aug-19	-
😑 A1	490	Brickwork upto lintel level	3	0	100%	15-Aug-19	17-Aug-1
😑 A1	500	Lintel & Sunshade shuttering work	1	0		19-Aug-19	-
- A1		Lintel & Sunshade barbending work	1	0		20-Aug-19	-
- A1		Lintel & Sunshade concrete	1	0		21 Aug 19	-
🗖 A1		Lintel & Sunshade Deshuttering	1	0		22-Aug-19	-
🗖 A1		Brickwork upto roof level	2	0		23-Aug-19	-
😑 A1	540	Fiixing of door and window frames	2	0	100%	26-Aug-19	27-Aug-1
🖕 RB.	тт	errace	94	0	100%	28-Aug-19	07-0ct-1
-	550	Laying of stub column reinforcement	2	0	100%	28-Aug-19	29-Aug-
😑 A1	560	Stub column shuttering	1	0	100%	30-Aug-19	30-Aug-
😑 A1	570	Pouring of concreete	1	0	100%	31-Aug-19	31-Aug-
😑 A1	580	Deshuttering	1	0	100%	06-Sep-19	06-Sep-
😑 A1	830	Raising of parapet wall	4	0	100%	09-Sep-19	13-Sep-
😑 A1	840	Waterr tank Works	18	0	100%	16-Sep-19	05-0ct-1
😑 A1	950						
ities	330	Weather course	1	0	100%	07-0ct-19	07-0ct-1
		ichedule Layout		Filter: All Ac	tivities		
			Original Duration				07-Oct-1
ayout: Cla ty ID <u> RB</u> .	assic S	Activity Name	Original Duration 73	Filter: All Ac Remaining Duration 1	tivities Schedule % 100%	Start 77	Finish 01-Jan-2
ayout: Cla ty ID <b>- RB.</b>	essic S E E: B.E.PL	chedule Layout Activity Name Xterior Works Plastering	Original Duration 73 5	Filter: All Ac Remaining Duration 1 0	tivities Schedule % 100% 100%	Start 7 08-0ct-19 08-0ct-19	Finish 01-Jan-2 14-Oct-1
ayout: Cla ty ID <b>B</b> RB.	essic S EEE 3.E.PL A1630	Activity Name	Original Duration 73	Filter: All Ac Remaining Duration 1	tivities Schedule % 100% 100% 100%	Start 77	Finish 01-Jan-2 14-Oct-1 08-Oct-1
ayout: Cla ty ID RB. RB.	E E: 3.E.PL A1630 A1670 3.E.W	Activity Name <b>xterior Works</b> Plastering Erection of Scaffolding Well plastering T Water & Sanitation Works	Original Duration 73 5 1 4 4	Filter: All Ac Remaining Duration 1 0 0 0 0 0	tivities Schedule % 100% 100% 100% 100%	Start 08-Oct-19 08-Oct-19 08-Oct-19 09-Oct-19 14-Oct-19	Finish 01-Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 26-Oct-1
ayout: Cla ty ID B RB. B RB RE RE RE	E E: 3.E.PL A1630 A1670 <b>3.E.W</b> A1600	Chedule Layout Activity Name Activity Name Election of Scaffolding Wall plastering AT Water & Sanitation Works	Original Duration 73 5 1 4 4 11 5	Filter: All Ac Remaining Duration 1 0 0 0 0 0 0 0	tivities Schedule % 100% 100% 100% 100% 100%	Start 08-0ct-19 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19	Finish 01-Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 26-Oct-1 18-Oct-1
ayout: Cla ty ID RB. RI RI RI	E E: 3.E.PL A1630 A1670 3.E.W A1600 A1680	ichedule Layout Activity Name <b>Xterior Works</b> Plastering Erection of Scaffolding Wall plastering AT Water & Sanitation Works Pipe works Water profing	Original Duration 73 5 1 4 11 5 2	Filter: All Ac Remaining Duration 1 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule % 100% 100% 100% 100% 100%	Start 08-0ct-19 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 19-0ct-19	Finish 01-Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 26-Oct-1 18-Oct-1 22-Oct-1
ayout: Cla ty ID	E E: 3.E.PL A1630 A1670 A1600 A1680 A1680 A1690	Chedule Layout Activity Name Activity Name Election of Scaffolding Wall plastering AT Water & Sanitation Works	Original Duration 73 5 1 4 4 11 5	Filter: All Ac Remaining Duration 1 0 0 0 0 0 0 0	tivities Schedule % 100% 100% 100% 100% 100% 100% 100%	Start 08-0ct-19 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19	Finish 01-Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 26-Oct-1 18-Oct-1 22-Oct-1 23-Oct-1
ayout: Cla ty ID	E E: 3.E.PL A1630 A1670 A1680 A1680 A1680 A1690 A1690 A1700 3.E.EV	Chedule Layout Activity Name  Clastering Erection of Scaffolding Wall plastering AT Water & Sanitation Works Water proofing Terrace looping Sanitaryware fixtures V Electrical works	Original Duration 73 5 1 4 11 5 2 2 2 3 3 12	Filter: All Ac Remaining Duration 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule % 100% 100% 100% 100% 100% 100% 100%	Start 7 08-0ct-19 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 12-0ct-19 22-0ct-19 23-0ct-19	Finish 01 Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 26-Oct-1 18-Oct-1 22-Oct-1 23-Oct-1 26-Oct-1 09-Nov-
ayout: Cla ty ID	E E: 3.E.PL A1630 A1670 A1600 A1680 A1690 A1690 A1690 A1690 A1690 A1690 A1690 A1690 A1690 A1690 A1670	Activity Name Activity Name Erection of Scaffolding Vell plastering AT Water & Sanitation Works Pipe works Velle proofing Terrace looping Sanitaryware fixtures V Electrical works Velling	Original Duration 73 5 1 1 4 4 11 5 2 2 2 3 3 12 4 4	Filter: All Ac Remaining Duration 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule % 100% 100% 100% 100% 100% 100% 100%	Start 7 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 14-0ct-19 22-0ct-19 22-0ct-19 23-0ct-19 26-0ct-19	Finish 01 Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 26-Oct-1 26-Oct-1 23-Oct-1 26-Oct-1 26-Oct-3 3-Oct-1 26-Oct-3 3-Oct-1 26-Oct-3 3-Oct-1
ayout: Cls ty ID	E E: 3.E.PL A1630 A1670 A1680 A1690 A1600 A1600 A1600 A1600 A1600 A1600 A1600 A1600 A1	Activity Name Activity Name Election of Scaffolding Wall plastering Torace looping Sanitaryware fixtures V Electrical works Viring Installation of panels	Original Duration 73 5 1 1 4 4 111 5 2 2 2 2 2 2 3 3 12 4 4 2	Filter: All Ac Remaining Duration 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule 5 100% 100% 100% 100% 100% 100% 100% 10	Start 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 14-0ct-19 22-0ct-19 23-0ct-19 23-0ct-19 26-0ct-19 26-0ct-19 26-0ct-19	Finish 01-Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 18-Oct-1 18-Oct-1 23-Oct-1 23-Oct-1 23-Oct-1 09-Nov- 31-Oct-1 02-Nov-
ayout: Cls ty ID RB. RI RI RI RI RI RI RI RI RI	E E: 3.E.PL A1630 A1670 A1680 A1680 A1680 A1690 A1700 A1	Activity Name Activity Name Erection of Scaffolding Vell plastering AT Water & Sanitation Works Pipe works Velle proofing Terrace looping Sanitaryware fixtures V Electrical works Velling	Original Duration 73 5 1 1 4 4 11 5 2 2 2 3 3 12 4 4	Filter: All Ac Remaining Duration 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule % 100% 1	Start 7 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 14-0ct-19 22-0ct-19 22-0ct-19 23-0ct-19 26-0ct-19	Finish 01 Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 28-Oct-1 28-Oct-1 23-Oct-1 23-Oct-1 23-Oct-1 23-Oct-1 09-Nov- 31-Oct-1 02-Nov- 05-Nov-
ayout: Cla ty ID RB. RI RI RI RI RI RI RI RI RI RI RI RI RI	E E: 3.E.PL A163( A167( A167( A169( A169( A169( A169( A170( A171( A171( A171( A172( A173( A1	Activity Name Activity Name Exterior Works Plastering Vall plastering Vall plastering Terace looping Sanitaryware fixtures V Electrical works Wiring Installation of panels Earthing Switches and fixtures Doors & Windows fini	Original Duration 73 5 1 4 11 5 2 2 2 3 3 12 4 4 2 2 2 3 3 3 2 2 2 3 3 3 2 2	Filter: All Ac Remaining Duration 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule 5 100% 1	Start 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 14-0ct-19 22-0ct-19 22-0ct-19 23-0ct-19 26-0ct-19 01-Nov-19 04-Nov-19 06-Nov-19	Finish 01-Jan-2 14-Oct-1 08-Oct-1 18-Oct-1 22-Oct-1 22-Oct-1 22-Oct-1 09-Nov- 31-Oct-1 02-Nov- 05-Nov- 05-Nov- 09-Nov- 11-Nov-
ayout: Cla ty ID RB. RI RI RI RI RI RI RI RI RI RI RI RI RI	E E: 3.E.PL A1630 A1670 A1690 A1690 A1690 A1690 A1690 A1690 A1690 A1690 A1690 A1620 A1670 A1700 A1	Chedule Layout Activity Name  Exterior Works Plastering Ferection of Scaffolding Wall plastering AT Water & Sanitation Works Pipe works Water proofing Terrace looping Sanitaryware fixtures V Electrical works Wiing Installation of panels Earthing Switches and fixtures Doors & Windows fini Windows shutter fixing	Original Duration 73 5 1 1 4 111 5 2 2 2 3 3 12 2 2 2 3 3 2 2 2 2 2	Filter: All Ac Remaining Duration 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule % 100% 100% 100% 100% 100% 100% 100% 1	Start 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 14-0ct-19 22-0ct-19 23-0ct-19 23-0ct-19 26-0ct-19 04-Nov-19 06-Nov-19 09-Nov-19	Finish 01 Jan 2 14-Oct-1 08-Oct-1 14-Oct-1 26-Oct-1 28-Oct-1 23-Oct-1 23-Oct-1 23-Oct-1 09-Nov- 31-Oct-1 05-Nov- 05-Nov- 05-Nov- 11-Nov-
ayout: Cla by ID RB. RI RI RI RI RI RI RI RI RI RI RI RI RI	E E: 3.E.PL 3.E.PL 4.163( 4.163( 4.169( 4.169( 4.169( 4.169( 4.179( 4.171( 4.172( 4.173( 4.172( 4.173( 4.162( 4.172( 4.172( 4.163( 4.162(	Activity Name Ac	Original Duration 73 5 1 1 4 4 11 5 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Filter: All Ac Remaining Duration 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule % 100% 100% 100% 100% 100% 100% 100% 1	Start 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 14-0ct-19 22-0ct-19 23-0ct-19 23-0ct-19 26-0ct-19 26-0ct-19 01-Nov-19 04-Nov-19 09-Nov-19 09-Nov-19	Finish 01 Jan-2 14-0ct.1 08-0ct.1 14-0ct.1 28-0ct.1 18-0ct.1 22-0ct.1 23-0ct.1 26-0ct.1 26-0ct.1 09-Nov. 31-0ct.1 09-Nov. 09-Nov. 09-Nov. 11-Nov. 26-Nov.
ayout: Cla by ID RB. RI RI RI RI RI RI RI RI RI RI RI RI RI	E E: 3.E.PL A1630 A167 A160 A160 A160 A160 A160 A170 A160 A170 A161 A171 A161 A171 A162 B.E.FF A1640	Chedule Layout Activity Name  Exterior Works Plastering Ferection of Scaffolding Wall plastering AT Water & Sanitation Works Pipe works Water proofing Terrace looping Sanitaryware fixtures V Electrical works Wiing Installation of panels Earthing Switches and fixtures Doors & Windows fini Windows shutter fixing	Original Duration 73 5 1 1 4 111 5 2 2 2 3 3 12 2 2 2 3 3 2 2 2 2 2	Filter: All Ac Remaining Duration 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule 9 00% 100% 100% 100% 100% 100% 100% 100%	Start 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 14-0ct-19 22-0ct-19 23-0ct-19 23-0ct-19 26-0ct-19 04-Nov-19 06-Nov-19 09-Nov-19	Finish 01 Jan 2 14-Oct-1 08-Oct-1 26-Oct-1 22-Oct-1 23-Oct-1 23-Oct-1 22-Oct-1 09-Nov- 05-Nov- 05-Nov- 05-Nov- 05-Nov- 11-Nov- 11-Nov- 11-Nov- 13-Nov-
ayout: Cla by ID RB. RE RE RE RE RE RE RE RE RE RE RE	E E: 3.E.PL A1630 A1670 A1680 A1680 A1680 A1680 A1600 A1600 A1620 A1710 A1620 A1620 A1640 A1740 A1640 A1740 A1640 A1640 A1670 A1770 A1670 A1770 A1670 A1770 A1670 A1770 A1	Activity Name  Activity Name	Original Duration 73 5 1 1 4 4 11 5 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Filter: All Ac Remaining Duration 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule % 100% 100% 100% 100% 100% 100% 100% 1	Start 08-0ct-19 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 14-0ct-19 22-0ct-19 23-0ct-19 23-0ct-19 26-0ct-19 01-Nov-19 04-Nov-19 09-Nov-19 09-Nov-19 12-Nov-19 14-Nov-19	Finish 01 Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 28-Oct-1 22-Oct-1 22-Oct-1 22-Oct-1 22-Oct-1 02-Nov- 31-Oct-1 02-Nov- 05-Nov- 05-Nov- 26-Nov- 26-Nov- 20-Nov- 20-Nov-
ayout: Cla by D RB. C RI C RI C C C C C C C C C C C C C C C	E E: 3.E.PL A1630 A1670 A1600 A1690 A1700 A1700 A1710 A1720 A1	ichedule Layout Activity Name <b>xterior Works</b> Plastering Erection of Scaffolding Wall plastering AT Water & Sanitation Works Water proofing Terrace looping Sanitaryware lixtures V Electrical works Wiining Installation of panels Earthing Switches and lixtures Doors & Windows fini Windows shutter fixing Floor finishes Leveling of floor Laying of floor Laying of mortar bed Polishing	Original Duration 73 5 1 1 4 4 11 5 2 2 2 2 2 3 3 12 4 4 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Filter: All Ac Remaining Duration 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule % % 100%	Start 08-0ct-19 08-0ct-19 08-0ct-19 09-0ct-19 09-0ct-19 14-0ct-19 13-0ct-19 22-0ct-19 23-0ct-19 23-0ct-19 23-0ct-19 23-0ct-19 23-0ct-19 23-0ct-19 03-Nov-19 03-Nov-19 03-Nov-19 12-Nov-19 12-Nov-19 14-	Finish 01-Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 25-Oct-1 22-Oct-1 22-Oct-1 22-Oct-1 09-Nov- 31-Oct-1 02-Nov- 05-Nov- 05-Nov- 05-Nov- 11-Nov- 11-Nov- 26-Nov- 20-Nov- 20-Nov
ayout: Cla ty D RB. RI RI RI RI RI RI RI RI RI RI RI RI RI	E E: 3.E.PL A163( A167( 3.E.W, A160( A169( A169( A169( A169( A171( A174( A174( A174( A174( A176( A174( A176( A174( A176( A174( A176( A174( A176( A174(	Chedule Layout Activity Name  Erection of Scaffolding  Wall plastering  AT Water & Sanitation Works  Pipe works  Water proofing  Terrace looping Sanitaryware fixtures  V Electrical works  Wiring Installation of panels Earthing Switches and fixtures Doors & Windows fini Windows shutter fixing Floor finishes Leveling of floor Laying of floor Laying of mortar bed Poishing Nating	Original Duration 73 5 1 1 4 11 1 5 2 2 2 3 3 12 4 4 2 2 3 3 2 2 2 2 2 2 2 2 2 2 2 6 6 6 6 4 4 2 8	Filter: All Ac Remaining Duration 1 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule 5 100% 1	Start 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 14-0ct-19 22-0ct-19 22-0ct-19 22-0ct-19 26-0ct-19 26-0ct-19 26-0ct-19 09-Nov-19 09-Nov-19 09-Nov-19 12-Nov-19 14-Nov-19 14-Nov-19 14-Nov-19 21-Nov-19 27-	Finish 01 Jan 2 14-Oct-1 08-Oct-1 14-Oct-1 26-Oct-1 18-Oct-1 23-Oct-1 23-Oct-1 23-Oct-1 23-Oct-1 03-Nov- 05-Nov- 05-Nov- 05-Nov- 05-Nov- 05-Nov- 05-Nov- 05-Nov- 20-No
ayout: Cle ty ID RB. RI RI RI RI RI RI RI RI RI RI RI RI RI	E E E 3.E.PL A1630 A1670 A1680 A1680 A1680 A1680 A1680 A1680 A1640 A1750 A1640 A1740 A1640 A1740 A1640 A1740 A1640 A1740 A1640 A1740 A1640	ichedule Layout Activity Name <b>xterior Works</b> Plastering Erection of Scaffolding Wall plastering AT Water & Sanitation Works Water proofing Terrace looping Sanitaryware lixtures V Electrical works Wiining Installation of panels Earthing Switches and lixtures Doors & Windows fini Windows shutter fixing Floor finishes Leveling of floor Laying of floor Laying of mortar bed Polishing	Original Duration 73 5 1 1 4 4 11 5 2 2 2 2 2 3 3 12 4 4 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Filter: All Ac Remaining Duration 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule % 100% 100% 100% 100% 100% 100% 100% 1	Start 08-0ct-19 08-0ct-19 08-0ct-19 09-0ct-19 09-0ct-19 14-0ct-19 13-0ct-19 22-0ct-19 23-0ct-19 23-0ct-19 23-0ct-19 23-0ct-19 23-0ct-19 23-0ct-19 03-Nov-19 03-Nov-19 03-Nov-19 12-Nov-19 12-Nov-19 14-	Finish 01 Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 28-Oct-1 22-Oct-1 22-Oct-1 22-Oct-1 22-Oct-1 22-Oct-1 02-Nov- 31-Oct-1 02-Nov- 05-Nov- 05-Nov- 26-Nov- 20-Nov- 20-Nov- 20-Nov- 20-Nov- 20-Nov- 20-Nov-
ayout: Cla ty D RB. RI RI RI RI RI RI RI RI RI RI RI RI RI	E E: A163 A163 A163 A163 A160 A164 A164 A177 A177	Chedule Layout Activity Name  Exterior Works Plastering Vall plastering Vall plastering Vall plastering Terrace looping Sanitaryware fixtures VELECTICAL WORKS Wiring Installation of panels Earthing Switches and fixtures Doors & Windows fini Vindows shutter fixing Floor finishes Leveling of floor Laying of tiles Laying of tiles Laying of motar bed Polishing Painting Applying putty on joints Applying putty on joints Applying primer Ist Coat of paint	Original Duration 73 5 1 1 4 11 5 2 2 2 2 3 3 12 4 4 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Filter: All Ac Remaining Duration 1 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule 5 100% 1	Start         7           08:0ct19         08:0ct19           08:0ct19         09:0ct19           14:0ct19         14:0ct19           14:0ct19         20:0ct19           24:0ct19         26:0ct19           26:0ct19         26:0ct19           26:0ct19         26:0ct19           06:Nov:19         09:Nov:19           09:Nov:19         09:Nov:19           12:Nov:19         12:Nov:19           14:Nov:19         14:Nov:19           27:Nov:19         30:Nov:19           30:Nov:19         30:Nov:19	Finish 01 Jan 2 14-Oct-1 08-Oct-1 14-Oct-1 26-Oct-1 26-Oct-1 23-Oct-1 23-Oct-1 23-Oct-1 23-Oct-1 23-Oct-1 03-Nov- 05-Nov- 09-Nov- 20-Nov- 20-Nov- 20-Nov- 20-Nov- 20-Nov- 20-Nov- 20-Nov- 21-Dec- 29-Nov- 05-Dec- 13-Dec-
ayout: Cle ty ID RB. RI RI RI RI RI RI RI RI RI RI RI RI RI	E E: 3.E.PL A1633 A1670 A1680 A1690 A1690 A1690 A1690 A1690 A1690 A1670 A1670 A1670 A1670 A1770 A1740 A1	Chedule Layout Activity Name  Control Vorks  Plastering Erection of Scaffolding Vali plastering  T Water & Sanitation Works  Pipe works Valing Terrace looping Terrace looping Sanitaryware fixtures  Viring Viring Viring Viring Installation of panels Earthing Switches and fixtures Doors & Windows fini Virindows shutter fixing Floor finishes Leveling of floor Laying of floes Laying	Original Duration 1 4 4 11 5 2 2 2 2 2 3 3 12 2 2 2 2 2 2 2 2 2 2 2	Filter: All Ac Remaining Duration 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule % 100% 100% 100% 100% 100% 100% 100% 1	Start 08-0ct-19 08-0ct-19 08-0ct-19 09-0ct-19 14-0ct-19 14-0ct-19 14-0ct-19 12-0ct-19 22-0ct-19 22-0ct-19 23-0	Finish 01 Jan-2 14-Oct-1 08-Oct-1 14-Oct-1 28-Oct-1 22-Oct-1 22-Oct-1 22-Oct-1 22-Oct-1 22-Oct-1 02-Nov- 31-Oct-1 02-Nov- 05-Nov- 20-Nov- 26-Nov- 20-Nov- 20-Nov- 20-Nov- 20-Nov- 20-Nov- 20-Nov- 20-Nov- 21-Dec- 13-Dec- 21-Dec-
ayout: Cle ty D RB. RI RI RI RI RI RI RI RI RI RI RI RI RI	E E: 3.E.PL A1630 A1670 A1680 A1680 A1690 A1690 A1690 A1690 A1700 A1710 A1710 A1710 A1710 A1710 A1710 A1740 A1	Chedule Layout Activity Name  Exterior Works Plastering Vall plastering Vall plastering Vall plastering Terrace looping Sanitaryware fixtures VELECTICAL WORKS Wiring Installation of panels Earthing Switches and fixtures Doors & Windows fini Vindows shutter fixing Floor finishes Leveling of floor Laying of tiles Laying of tiles Laying of motar bed Polishing Painting Applying putty on joints Applying putty on joints Applying primer Ist Coat of paint	Original Duration 73 5 1 1 4 11 5 2 2 2 2 3 3 12 4 4 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Filter: All Ac Remaining Duration 1 1 0 0 0 0 0 0 0 0 0 0 0 0 0	tivities Schedule % % 100%	Start         C           08:0ct19         08:0ct19           08:0ct19         09:0ct19           14:0ct19         14:0ct19           14:0ct19         20:0ct19           24:0ct19         26:0ct19           26:0ct19         26:0ct19           26:0ct19         26:0ct19           06:Nov:19         09:Nov:19           09:Nov:19         09:Nov:19           12:Nov:19         12:Nov:19           14:Nov:19         14:Nov:19           27:Nov:19         30:Nov:19           30:Nov:19         30:Nov:19	Finish 01 Jan 2 14-Oct-1 08-Oct-1 14-Oct-1 26-Oct-1 26-Oct-1 22-Oct-1 22-Oct-1 22-Oct-1 12-Nov-1 31-Oct-1 23-Oct-1 12-Nov-1 13-Nov-1 13-Nov-1 20-Nov-1 13-Nov-1 20-Nov-1 20-Nov-1 20-Nov-1 20-Nov-1 20-Nov-1 20-Nov-1 13-Nov-1 20-Nov-1 20-Nov-1 13-Nov-1 21-Dec-1 13-Dec-1 21-Dec-1 01-Jan 2

Fig 6. Project activities


- Relationship between activities then need to be assigned to form a project network which represent the flow of work to be done. Relationships can either be *finish to start, finish to finish, start to start* or *start to finish*, depending on the level of importance of each activity. Doing so helps identify *critical activities* and the *critical path* for the project
- A gantt chart is generated to represent the timeline of work to be done in the project. The Primavera P6 gantt chart helps us visualize the project's schedule and helps us

tabulate the start and finish time of the activities. This makes the schedule more flexible to work with





### Earned Value Management of a Villa Construction project using Primavera P6






Fig 7. Project baseline

- Critical activities represent the activities which are mandatory to prevent the delay of the project. These activities must start and finish on time to ensure that the work stays on schedule
- The *planned duration* of the activities then needs to be entered. This usually depends on the activity and amount of the work represented by it. The *actual duration* will then be determined after the activity actually get completed
- This duration is dependent on the start and finish dates of the activity. Primavera offers four types of activity dates: *actual start, actual finish, planned start* and

*planned finish.* These also govern the relationship between various activities and interlink them together

- Primavera also offers *activity cost* parameters which define the costs incurred over the course of the completion of the activity
- Each activity further needs to have *resources* allocated to it to determine activity cost. In our study we divided known available resources into two types: labor and nonlabor
- For example, a mason is a labor resource whereas a concrete vibrator is a non-labor resource
- Each of these resources have fixed rates of pay which determine the non-material cost incurred by the activity.

RESOURCE NAME	<b>RESOURCE TYPE</b>	RATE (COST/DAY)
MASON	LABOUR	RS. 850
MAZDOOR	LABOUR	RS. 700
MATE	LABOUR	RS. 650
BARBENDER	LABOUR	RS. 700
PAINTER	LABOUR	RS. 750
BHISTI	LABOUR	RS. 600
CARPENTER	LABOUR	RS. 700
PLUMBER	LABOUR	RS. 750
PLUMBER ASSISTANT	LABOUR	RS. 650
MIXER	NON LABOUR	RS. 1300
ELECTRICIAN	LABOUR	RS. 750
ELECTRICIAN ASSISTANT	LABOUR	RS. 650
MIXER OPERATOR	LABOUR	RS. 650
VIBRATOR	NON LABOUR	RS. 500

### Table 2. Rate of allocated resources as per IS 7272:1974 and Delhi Analysis of Rates

- The resources were assigned to each activity based on the work done and in accordance with *IS* 7272:1974 and *Delhi Analysis of Rates*. The structural details were procured from the firm and were used for assigning resources to each activity.
- As an example, during excavation the measurements are done in cubic meter where the length and breadth are taken from the structural drawings and a mean value of depth is used to calculate volume of excavations needed to analyze rate of resource

allocation. In the study under consideration five excavations of dimensions 1'x9" were done, four excavations of dimensions 1'3"x9" were done and finally two excavations of dimensions 1'9"x9" were done. Similarly, such calculations were done for estimating and assigning of resources to all other activities

- *Earned Value Analysis* is then performed where the actual cost of the project is compared against the budgeted cost with both time and scope as governing parameters. Performing EVM on a project can give us details on the budgeting and resource usage of the work done and analyze whether or not the work done is cost effective
- Schedule variance (SV): determines whether a project is behind or ahead of the schedule and is calculated by subtracting planned value from the earned value.

Schedule variance = Earned value (EV) -Planned value (PV)

• Schedule performance index (SPI): indicates the efficiency with which the project team is using its time

Schedule performance index = Earned value / Planned value

• Time estimates at completion (EAC): generates a rough estimate of when project will be completed

*Estimate at complete (EAC) = (BAC/SPI)/(BAC/months)* 

BAC = Budget at completion

- Cost variance (CV): indicates whether a project is under or over its planned budget *Cost variance* (*CV*) = *Earned value* (*EV*) - *Actual cost* (*AC*)
- Cost performance index (CPI): gives a clear indicator of the cumulative cost efficiency of the project

*Cost performance index (CPI) = Earned value (EV) / Actual cost (AC)* 

### Conclusions

The progress of work done during the course of completion of a construction project can be measured and tracked by means of proper planning and scheduling. This allows project managers to assess the initial scope of the project and also measure the change in scope in case of any setbacks. Further a proper management system helps mitigate risks and ensures that the management team is always able to plan around any obstacle encountered.

The main focus of the study was to highlight the importance of said planning in construction projects and offer up Primavera P6 as an effective tool for project managers to exploit. This was achieved through extensive literature surveys and then a practical problem was undertaken using the software to show its versatility. Results of this report highlight the disadvantages of improper management systems (in SMEs) and the importance of efficient management software like Primavera.

### Summary of results derived

- A total of 92 activities were mapped under work to be done for the project
- The project completion date according to the planned schedule was on 31<sup>st</sup> December, 2019
- The actual project was delayed for around 2 months and wrapped up on the 7<sup>th</sup> of February, 2020
- The budget allocated for one standalone 4BHK villa was valued around Rs. 60,00,000 as of 2019
- The cost of labour was calculated at around Rs. 13,11,933
- The Cost Performance Index of the project was around 0.46 indicating that the project was under budgeted. This is a direct consequence of lack of planning, monitoring and lack of consideration of miscellaneous constraints
- Proper delay analysis considerations were not under order and the ensuing delays are subject to proof. The team appears to have severely underestimated the unpredictability of the Chennai monsoon cycle thus resulting in overtime work
- Primavera P6 proves to be an efficient tool in aiding management of construction projects and helps immensely in monitoring and controlling the scope of work to be done

### References

- Chan J P, JuHyung Kim, Jae-Jun Kim & Yong C Y (2007). *Management of Daily Progress in a Construction Project of Multiple Apartment Buildings*. Journal of Construction Engineering and Management. Vol. 3, Issue 133. [242 - 253]
- Daniel C L, Gursel A S, Julian Gonzalez & Yates J K (2009). Construction Project Scheduling with Time, Cost, and Material Restrictions Using Fuzzy Mathematical Models and Critical Path Method. Journal of Construction Engineering and Management. Vol. 10, Issue 135. [1096 – 1104]
- Anurag Mahure & Amitkumar Ranit (2018). Project management using Primavera P6.International Journal of Engineering Research and Technology. Vol. 7, Issue 4. [241 - 244]
- Unmesh Y Polekar & Rohit R Salgude (2015). *Planning, Scheduling and Tracking of a residential Project using Primavera Software*. International Journal of Advance Research in Computer Science and Management Studies. Vol. 3, Issue 5.
- Burke R (2003). *Project Management, Planning and Control Techniques.* Chichester, John Wiley and Sons.Inc. 2003
- A Naderpour & M Mofid (2011). Improving Construction Management of an Educational Center by Applying Earned Value Technique. Procedia Engineering. Vol. 14. [1945 – 1952]
- Alberto De Marco & Timur Narbaev (2013). Earned value-based performance monitoring of facility construction projects. Journal of Facilities Management. Vol. 11, Issue 1. [69-80]

- Tan Chin Keng & Najihah Shahdan (2015). The application of earned value management(EVM) in construction project management. Journal of Technology Management and<br/>Business.Business.Retrievedhttps://publisher.uthm.edu.my/ojs/index.php/jtmb/article/view/1096
- Ankur Verma, K K Pathak & R K Dixit (2014). Earned Value Analysis of Construction Project at Rashtriya Sanskrit Sansthan, Bhopal. International Journal of Innovative Research in Science, Engineering and Technology. Vol. 3, Issue 4. [11350 – 11355]